

**PROPOSED RESIDENTIAL APARTMENT ON PLOT NO
12715/8491 AND 8492 SYOKIMAU - MACHAKOS FOR
JANE WANJIKU MWANIKI**

BILLS OF QUANTITIES

PROPOSED RESIDENTIAL APARTMENT ON PLOT NO 12715/8491 AND 8492 SYOKIMAU - MACHAKOS FOR JANE WANJIKU
MWANIKI

ITEM	DESCRIPTION	UNIT	QTY	RATE	AMOUNT(KES)
	<u>BILL NO. 1- MAIN HOUSE</u>				
	<u>ELEMENT 01</u>				
	<u>Site clearance SUBSTRUCTURE (All provisional)</u>				
A	Clear site of all grass, shrubs, small trees and grub up roots and burn the arising debris.	SM	822	50.00	41,100.00
B	Excavate from reduced level; not exceeding 1.5 m deep for strip foundations	CM	282	350	98,700.00
C	Ditto for column bases	CM	326	350	113,960.00
D	Excavate to reduce level; average 300mm deep	SM	730	150	109,500.00
	<u>Filling</u>				
E	Return, fill and ram with imported murram	CM	396	100	39,600.00
	<u>Disposal</u>				
F	Remove surplus soil from site to a place approved by local authority as dumping site	CM	635	150	95,250.00
	<u>Planking and strutting</u>				
G	Allow for planking and strutting to excavations and for keeping bottoms free from fallen materials	Item			30,000.00
	<u>Disposal of water</u>				
H	Allow for keep excavations free of spring, underground or running water including any necessary pumping, bailing or other approved means	Item			30,000.00
	<u>Mass concrete class 15(1:3:6):in</u>				
I	50 mm Thick blinding under strip foundations	SM	133	380	50,464.00
J	Ditto under column bases	SM	192	380	72,960.00
	<u>Vibrated reinforced insitu concrete class 20/20; with minimum cube crushing strength of 25N/mm² at 28 days; in</u>				
K	Strip footing	CM	33	11,500	379,500.00
L	Column bases	CM	74	11,500	853,300.00
M	Substructural columns	CM	9	11,500	103,500.00
N	150 mm ground floor slab	CM	822	1,725	1,417,950.00
	<u>Mesh fabric reinforcement to B.S. 4483</u>				
O	Reference A142; mesh 200 x 200 mm weight 2.22 kgs per square metre (measured net-no allowance made for laps); including bends, tying wire and distance blocks. Rate to include laps	SM	822	450	369,900.00
	<u>Hardcore fill</u>				
P	Hardcore of approved inert material: well watered and compacted in 200 mm thick (maximum) layers	CM	183	900	164,250.00
	<i>Carried forward</i>				3,969,934.00

PROPOSED RESIDENTIAL APARTMENT ON PLOT NO 12715/8491 AND 8492 SYOKIMAU - MACHAKOS FOR JANE WANJIKU MWANIKI

[illegible]

PROPOSED RESIDENTIAL APARTMENT ON PLOT NO 12715/8491 AND 8492 SYOKIMAU - MACHAKOS FOR JANE WANJIKU MWANIKI

ITEM	DESCRIPTION	UNIT	QTY	RATE	AMOUNT(KES)
	ELEMENT NO 2 - SUPERSTRUCTURE				
	<u>Sawn timber formwork: to</u>				
	<u>Beams ;</u>				
A	Sides and soffits.	SM	1,764	400	705,600.00
	<u>Columns ;</u>				
B	Vertical sides	SM	767	400	306,720.00
	<u>Slab</u>				
C	Soffits of Suspended Slabs	SM	2,016	400	806,400.00
	<u>Staircase</u>				
D	Ditto to landings.	SM	22	400	8,640.00
E	Slopping soffits of staircase.	SM	58	400	23,040.00
F	Risers and edges of stairs; 75 - 150mm girth.	Lm	180	70	12,600.00
G	Edges of suspended slabs; 75 - 150mm girth.	Lm	673	70	47,124.00
	<u>Supply and fix High tensile steel reinforcements bar in structural concrete work including cutting, bending, hoisting, tying wire, spacing blocks and supporting all in position as required to B.s standard 4461: Bar size;</u>				
H	8 mm diameter	Kg	6,934	140	970,732.00
I	10 mm diameter	Kg	21,648	140	3,030,720.00
J	12 mm diameter	Kg	7,487	140	1,048,208.00
K	16 mm diameter	Kg	22,332	140	3,126,480.00
L	20 mm diameter	Kg	3,715	140	520,128.00
M	25 mm diameter	Kg	3,711	140	519,540.00
	<u>Vibrated reinforced insitu concrete class 20/20; with minimum cube crushing strength of 25N/mm² at 28 days; in</u>				
N	150mm thick Horizontal suspended slab	SM	2,344	1,725	4,042,710.00
O	Beams	CM	168	11,500	1,932,000.00
P	Columns	SM	78	11,500	892,400.00
	<u>Staircase</u>				
Q	150 mm thick suspended landing	SM	22	1,725	37,260.00
R	Steps and waist	CM	10	11,500	110,400.00
	R. C SUPERSTRUCTURE CARRIED TO SUMMARY				18,140,702.00

PROPOSED RESIDENTIAL APARTMENT ON PLOT NO 12715/8491 AND 8492 SYOKIMAU - MACHAKOS FOR JANE WANJIKU MWANIKI

[illegible]